


OVERFLOW DRAIN WITH STANDPIPE AND OPTIONAL DOME FOR MEMBRANE FLOOR AREAS

Specification: MIFAB® Series F1100-C-W(D) lacquered cast iron floor drain with anchor flange, cast iron membrane clamp ring with primary and secondary weepholes for waterproofing membrane, adjustable 4" (102) diameter ABS standpipe and stainless steel dome. (For non-membrane floors, use MIFAB F1100-W(D) Series.)

Function: Used in an overflow drain in decorative fountains, pools, fish ponds and other similar areas. The dome assembled to the top of the standpipe prevents floating debris from entering the drain line. Membrane clamp is provided to secure the waterproofing membrane.



•	A1 BODY
	A1-W
	OR
	A1-WD
	0
	A1-C1

PARTS:

PIPE	BODY HEIGHT					
SIZE	NO HUB	PUSH	THREADED	INSIDE	PVC/ABS	
	(STANDARD)	ON (P)	(T)	CAULK (X)	(-30)/(-31)	
2" (51)	3" (76)	3 3/8" (86)	2 1/4" (57)	3 3/4" (95)	2 15/16" (75)	
3" (76)	3" (76)	3 3/8" (86)	2 5/8" (67)	3 3/4" (95)	3 3/4" (95)	
4" (102)	3" (76)	3 3/8" (86)	2 5/8" (67)	3 3/4" (95)	3 3/4" (95)	
5" (127)	3" (76)		2 5/8" (67)	3 3/4" (95)		
6" (152)	3 1/4" (83)	6 1/2" (165)				

HS-1

F1100-C-W(D) Series meets ANSI-ASME floor drain standard A112.6.3-2001

SUFFIX	OPTIONAL VARIATIONS	SUFFIX	OPTIONAL VARIATIONS
-6	Security screws (T-20 Torx & pin)	-90	Threaded side outlet (2", 3", 4") (cast iron only)
-7	1/2" trap seal primer connection	-90NH	No hub side outlet (2", 3", 4") (cast iron only)
-8	Backwater valve (2", 3", 4")	-95	Client logo
-11	Acid resistant epoxy coated body	-BA	Buy American Act compliant product
-13	Galvanized body	-C2	High rough-in membrane clamp (min. 1 9/16" (40))
-15	Extension	(Standard)	No hub outlet
-21	Secondary flat stainless steel strainer (2", 3", 4")	-MG	MI-GARD Floor Drain Trap Sealer (2", 3" or 4")
-28	Stainless steel body (Type 304)	Р	Push on outlet
-30	PVC socket connection body	-PA	Pennsylvania Steel Act compliant product
-31	ABS socket connection body	Т	Threaded outlet (2", 3", 4")
-34	Closure plug	X	Inside caulk outlet
-40	Underdeck clamp	-Z	Extended wide elastomeric flange
-41	Sump receiver		

CALIFORNIA PROPOSITION 65 WARNING. This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm.

Job Name:	Page No:
Section No:	Contractor:
Schedule No:	Purchase Order No:

MIFAB reserves the right to make changes in material and design without formal notice and obligation.

USA: 1-800-465-2736 www.mifab.com CAN: 1-800-387-3880